



T & S Custom Curbing, Inc.

118 Woodstock St
Fruita, CO 81521

Phone # 970-270-5927
Fax # 970-858-6554

robert@tandslandscape.com

Estimate

Date	Estimate #
4/15/2017	784

<p>Montclair Subdivision HOA Contact: Tim Laudick 970-618-3531</p>
--

Description	Qty	Cost	Total
Bldg 805-807 total 282' linear feet		1,367.70	1,367.70
Bldg 811-813 total 262' linear feet		1,270.70	1,270.70
Bldg 817-819 total 215' linear feet		1,042.75	1,042.75
Bldg 823-825 total 90' linear feet		436.50	436.50
Bldg 843-847-851 total 303' linear feet		1,469.55	1,469.55
Bldg 818-820 222' linear feet		1,076.70	1,076.70
Bldg 844-848-852 total 322' linear feet		1,561.70	1,561.70
Bldg 856 (along path on North side) total 148' linear feet		717.80	717.80
<p>Totals include removing and hauling away metal edging, moving sprinklers as needed, cutting sod and hauling from site, moving back the rock to accommodate curbing, installation of grey concrete curbing and placing rock back against curb once completed. Angle or Mower profile. Prep cost per foot \$2.00, curbing installation cost per foot \$2.85.</p>			

We look forward to working with you!	Total	\$8,943.40
--------------------------------------	--------------	------------

T&S is not responsible for any settling that may occur on or around utility lines or boxes. Any changes from this estimate can and will affect the cost of the job. All of the work performed carries a one year warranty against materials and workmanship. Required locates of under ground utilities will be performed prior to any excavation.